



LT	NO	ALTERATIONS
A	1	REINFORCED STRUCTURAL DECK SCHEDULE 1, HODDERS AND DECK

- NOTES**
1. PLACE 500 LBS OF SOLID LEAD PIGS TO TRIM FIRST BEAT. SUBS. BOATS SHALL HAVE 4000 LBS. IN ONE CASTING.
  2. TO REPLACE INTERRUPTED STRENGTH IN WAY OF MAST DUE TO LACK OF A CONTINUOUS AT-WATERSHIP MEMBER, AN EXTRA SEP. LAMINATE CON- SISTING OF 27 OZ. W.R. & BRONZING INSIDE WITH 17 1/2 OZ. MAT TO 1/8" THICK MIN. SHALL BE ADDED TO THE UNDER- SIDE OF THE TOUNG SANDWICH - EXTENDING DOWN THE SIDES OUT UNDER THE MAIN DECK IN WAY OF THE CHAIN PLATES. THE LAMINATE SHALL BE APPROXIMATELY 40" LONG AND ART. 2'-0" FWD & AFT OF THE E. OF MAST.
  3. THE TOPSIDE LAMINATE FOR 1/4 LQR FROM EACH END OF THE MAST MAY BE REDUCED BY ONE 1/2 OZ. W.R.

**RESERVATIONS**  
 1. DETAILS, EXCEPT AS NOTED, ARE IN FURTHER DEVELOPMENT.

SEABREEZE  
**DESIGN #212**  
**CONSTRUCTION PLAN**  
 SE A  
**34'6" AUXILIARY SLOOP**  
 SE B  
**ALLIED BOAT CO. INC.**  
 SCALE 3/4" = 1'-0"  
 DESIGNED BY  
**MAC LEAR & HARRIS**  
 11 EAST 44th ST. NEW YORK, N.Y. 10017  
 (212) 996-6440

FEB 1966 234 UWA 712-E-17A